

**Ross Township
2016 Pavement Maintenance Program
Approximate Quantities per Street
March 18, 2016**

PROPOSED SUPERPAVE STREETS

STREET NAME	FROM:	TO:	Length (FT)	Area (SY)	3.5" +/- Milling (SY)	2" 19mm Binder (TON)	4" 25mm Binder (TON)	1.5" 9.5mm 0.3 ESAL (SY)	Bituminous Wedge Curb	Base Repair (SY)	MH / Inlet Adjustments (EA)	Rain Collector or (LF)	ADA Ramp (S.F.)	Concrete Sidewalk (S.F.)	Concrete Curb (L.F.)	Concrete Cheekwall (L.F.)	Concrete Wheel Stop (EA)	Traffic Loop (EA)	Line Striping (LS)	Traffic Control / Restoration	Type of Replacement / Comment	
					Item #1	Item #2	Item #3	Item #4	Item #5	Item #6	Item #7	Item #8	Item #9	Item #10	Item #11	Item #12	Item #13	Item #14	Item #15	Item #16		
Houston Road	Park Place	McKnight Road	1140	2,950	2,950	410	0	2,950	2,280	0	0	0	0	0	0	0	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
Decker Lane	Perry Highway	Terminus	355	500	500	82	0	500	710	0	0	0	0	0	0	0	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
Oak Street	Klemont Ave	Alley B	150	300	300	44	0	300	300	0	0	0	56	12	13	10	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
Spruce Valley Drive	Meadow Ct	Center Ave	910	3,100	3,100	409	0	3,100	1,820	0	0	0	0	0	0	0	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
Preston Avenue	Bascom Ave	Terminus	1185	2,400	2,400	353	0	2,400	2,370	0	0	0	0	0	0	0	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
Criders Lane	Evergreen Road	Terminus	1170	1,900	1,900	297	0	1,900	2,340	0	0	0	0	0	0	0	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
Elm Street	Lincoln Avenue	Main Blvd	1050	2,500	2,500	354	0	2,500	2,100	0	0	0	0	0	0	0	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
Laurelwood Drive	Charterwood Dr	Ennerdale Lane	1545	4,700	4,700	633	0	4,700	3,090	0	0	0	0	0	0	0	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
Browns Lane	Three Degree	Marie Drive	1450	4,200	4,200	522	0	4,200	1,600	0	0	0	163	289	111	0	0	1	1	1	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
Church Road	Babcock Blvd	Greenhill	930	2,500	2,500	345	0	2,500	1,860	0	0	0	0	0	0	0	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
Benton Avenue	Bascom Avenue	Township Line	1270	3,130	3,130	440	0	3,130	2,540	0	0	0	0	0	0	0	0	0	0	1	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
Perry Lane	Perry Highway	Terminus	1500	3,500	3,500	498	0	3,500	3,000	0	0	0	0	0	0	0	0	1	1	1	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
Evergreen Park	Phase II Parking Lot			750	0	0	180	750	400	0	0	0	0	0	0	0	9	0	0	0	1	4" 25.0 mm Binder with 1 1/2" 9.5 mm Wearing Ross DPW will complete Line Striping of Parking Lot
Totals:					32,430	31,680	4,385	180	32,430	24,410	0	0	0	219	301	124	10	9	2	3	13	