Ross Township
2016 Pavement Maintenance Program
Approximate Quantities per Street
March 18, 2016

PROPOSED ID-2 STREETS

BASE BID

STREET NAME	FROM:	TO:	Length (FT)	Area (SY)	3.5"+/- Milling (SY)	2" 19mm Binder (TON)	4" 25mm Binder (TON)	.5" 9.5mm 0-0.3 ESALS (SY)	Bituminous Wedge Curb	Base Repair (SY)	MH / Inlet Adjustment (EA)	Rain Conductor (LF)	ADA Ramp (S.F.)	Concrete Sidewalk (S.F.)	Concrete Curb (L.F.)	Concrete Cheekwall (L.F.)	Concrete Wheel Stop (EA)	Traffic Loop (EA)	Line Striping (LS)	Traffic Control / Restoration	Type of Replacement / Comment
					Item #1	Item #2	Item #3	Item #4	Item #5	Item #6	Item #7	Item #8	Item #9	Item #10	Item #11	Item #12	Item #13	Item #14	Item #15	Item #16	
Casper Avenue	Amherst Ave	Princeton Ave	250	600	600	85	0	600	500	0	0	0	0	0	0	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
William Street	Poland Ave	Bostwick Dr	254	600	600	86	0	600	520	0	0	0	0	0	0	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
Norwich Avenue	Evergreen Heights Road	Terminus	270	550	550	81	0	550	540	0	0	0	0	0	0	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
Haviland Drive	Wedgewood Rd	E. Wedgewood Rd	325	1,100	1,100	145	0	1,100	650	0	0	0	0	0	0	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
Kenyon Road	Kenyon Road	Gass Road	245	500	500	73	0	500	490	0	0	0	0	0	0	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
Princeton Avenue	Springview Ave	Casper Ave	180	500	500	69	0	500	360	0	0	0	0	0	0	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
Rolling Drive	Cul-de-sac	Terminus	1060	2,600	2,600	366	0	2,600	2,120	0	0	0	0	0	0	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
Chestnut Avenue	Township Line	Division St	655	1,100	1,100	170	0	1,100	1,310	0	0	0	0	0	0	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
Cyrano Avenue	Terminus	Terminus	380	600	600	95	0	600	760	0	0	0	0	0	0	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
Division Street	Chest Nut Ave	Bostwick Dr	515	1,300	1,300	182	0	1,300	1,030	0	0	0	0	0	0	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
Pearl Avenue	Bellevue Road	Terminus	770	2,300	2,300	311	0	2,300	1,540	0	0	0	0	0	0	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
Stevens Street	E Bellevue Ave	Sunflower Ave	240	500	500	73	0	500	480	0	0	0	0	0	0	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
Oak Drive	York Drive	Terminus	670	1,700	1,700	237	0	1,700	1,340	0	0	0	0	0	0	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
Towers Terrace	Burkhart St	Terminus	725	500	500	109	0	500	1,450	0	0	0	0	0	0	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
Blaze Drive	Blaze Dr	Culdesac	155	800	800	100	0	800	310	0	0	0	0	0	0	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
Kentzel Road	116 Kentzel	Siebert Road	760	1,690	1,690	243	0	1,690	1,520	0	0	0	0	0	0	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
3rd Street	5th Ave	6th Ave	355	1,100	1,100	148	0	1,100	710	0	0	0	0	0	0	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
9th Avenue	13th Avenue	10th Avenue	1190	2,800	2,800	397	0	2,800	2,380	0	0	0	0	0	0	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
E Bellevue Avenue	Township Line	Clearview Ave	465	1,100	1,100	156	0	1,100	930	0	0	0	0	0	0	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
Rodenbaugh Ave	Adna Street	Ivory Road	1160	2,000	2,000	305	0	2,000	2,320	0	0	0	0	0	0	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
4th Avenue	3rd Street	2nd Street	1280	3,420	3,420	472	0	3,420	2,560	0	0	0	0	0	0	0	0	0	0	1	2" 19.0 mm Binder with 1 1/2" 9.5 mm Wearing
Totals:				27,360	27,360	3,901	0	27,360	23,820	100	10	100	0	0	0	0	0	0	0	21	