

**Ross Township
2025 Paving Program
Contract 5/2025
Final Paving List with Work Orders**

STREET NAME	FROM:	TO:	Length (FT)	Width (FT)	Approx. Area (SY)	3.5"+/- Milling (SY)	2" 19mm Binder (TON)	1.5" 9.5mm 0-0.3 ESALS (SY)	3/4" Scratch Course (TON)	Bituminous Wedge Curb (LF)	MH/Inlet Adjustments	ADA Ramp (EA)	Traffic Control / Restoration (EA)
Deimling Road (Section 1 - Half Lane)	Perry Hwy	Existing 1	149	8.7	154	154	23	154	0	159	2	0	1
Deimling Road (Section 2 - Full Lane)	Existing 1	Hieber Avenue	79	22.8	214	214	30	214	0	169	2	0	0
Harding Road	McIntyre Road	Terminus (W)	1,211	24.1	3,469	3,469	479	3,469	0	2,592	2	0	1
Hieber Avenue	Deimling Road	Existing 2	68	23.3	188	188	26	188	0	146	2	0	1
Hieber Avenue	Existing 2	Existing 3	134	18.9	301	301	44	301	0	287	2	0	0
Link Avenue	Minnock Drive	Westmont Drive	705	25.1	2,100	2,100	288	2,100	0	1,509	2	0	1
Minnock Drive	Link Avenue	Link Avenue	1,026	24.3	2,959	2,959	408	2,959	0	2,196	2	0	1
Nocklyn Drive	Rochester Road	Nocklyn Drive	1,583	27.3	5,137	5,137	692	5,137	0	3,388	2	0	1
Ridgeside Road	Hillendale Road	Terminus (W)	507	25.2	1,519	1,519	208	1,519	0	1,085	2	0	1
Rose Avenue	Gass Road	Highview Avenue	582	25.3	1,753	1,753	239	1,753	0	1,245	2	0	1
Tadmar Avenue	Link Avenue	Terminus (W)	1,713	29.4	5,983	5,983	796	5,983	0	3,666	2	0	1
Timberlane Drive (1)	Gass Road	Peony Avenue	621	32.9	2,429	2,429	317	2,429	0	1,329	2	0	1
Timberlane Drive (2)	133 Timberlane Drive	Terminus (W)	564	32.0	2,145	2,145	281	2,145	0	1,207	2	0	1
Valley Hi Drive	Gass Road	Terminus (W)	1,386	34.8	5,739	5,739	631	5,739	0	0	2	0	1
Wedgewood Drive	Gass Road	Winslow Drive	2,045	31.4	7,646	7,646	1,005	7,646	0	4,376	2	0	1
Municipal Center Zone 3	Zone 1	Zone 4			6,548	6,548	776	6,548	0	1,491	2	0	1
Municipal Center Zone 4	Zone 2	Terminus (N)			3,821	3,821	493	3,821	0	1,943	2	0	1
Bennington Woods Drive	McIntyre Road	Roundabout	2,154	30.7	7,855	7,855	1,041	7,855	0	4,723	2	0	1
			14,527		59,962	59,962	7,777	59,962	0	31,510	36	0	16